



c/46

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE
NEW DELHI- 110 001

No.F6/DFS/MS/School/2025/NDZ/ 500

Dated: 16/04/2025

FIRE SAFETY CERTIFICATE

Certified that the D.A.V. Public School located at Mausham Vihar, Delhi-110051, comprised of ground plus two upper floors & Porta cabin at terrace (closed), owned/occupied by D.A.V. Public School was issued FSC vide letter No. F.6/DFS/MS/School/2022/NDZ/164 dated 11/02/2022. The school building was re-inspected by the officers concerned of this department on 29/03/2025 in the presence of Mr. Rajesh and observed that all the fire prevention and fire safety arrangements provided in the premises found in good working condition. The premises have therefore deemed complied with rule 33 of Delhi Fire Service Rules 2010 and that the building is fit for occupancy class "Educational" (Group-B) with effect from 16 / 04 /2025 for a period of three years in accordance with rule 36 unless renewal under rule 37 or sooner cancelled under rule 40 and subject to compliance of the conditions under rule 38 of the DFS rules, 2010.

Issued on...16/04/2025.....at New Delhi by.

ATUL GARG)
DIRECTOR
DELHI FIRE SERVICE

To,

The Principal,
D.A.V. Public School located at Mausham Vihar, Delhi-110051

Copy:-

The Dy. Director of Education,
D-Block, Anand Vihar, Delhi-110092

Conditions for the validity of Fire Safety Certificate

1. Fire Safety Certificate is valid for Ground to 2nd floor only, Porta cabin constructed at terrace has been closed and not in used failing which FSC could be treated null and void.
2. All the means of escape shall be kept free of all type of obstruction all the time.
3. All the employees shall be acquainted with the use and maintenance of all fire equipments and method of smooth and speedy safe evacuation of occupants in case of emergency.
4. All the fire fighting equipment shall be maintained in perfect working condition all the time and any lapse rendering non-functional of fire safety measures, management shall be responsible.
5. Any deviation, with regards to construction, ventilation, occupancy, electric installation etc. may be got verified from the concerned authorities.
6. This Fire Safety Certificate may not be treated in any case for regularizations of unauthorized construction /unauthorized use of land if any.
7. The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rule 2010. The form is available on www.dfs.delhigovt.nic.in
8. The owner / occupier shall apply for renewal of this Fire Safety Certificate of the Director in Form 'J' [sub rule (1) of rule (37)] along with a copy of this Certificate, Six Months prior to its expiry.

INSPECTION REPORT

1. Name & address of the building : D.A.V. Public School
Mausham Vihar, Delhi-51
2. Building is comprised of : Ground Plus two upper floors
Porta cabin at terrace (closed)
3. Type of Occupancy : Educational
4. Type of Case : Renewal
5. Details of Previous NOC letter : F.6/DFS/MS/School/2022/NDZ/164 dt 11/02/2022
6. Fire Safety direction letter No : NBC part IV
7. Date of Inspection : 29/03/2025
8. Name of the Inspecting officers : DO, A.K. Jaiswal & ADO (Shd.) Deepak Kumar
9. Name and designation of Officer
from the building side : Mr. Rajesh
10. Year of Construction : 2009
11. Applicant's letter No : SLSDAVPS/2024-2025/1031 Dated- 15/02/2025

Sr. No	Minimum Standards on fire prevention and fire safety U/R33	NBC Part IV/BBL Requirement	Provided at Site	Remarks MR/NMR
01	Access to building.			
	<ul style="list-style-type: none"> Road width Gate width Width of internal road 	06 mtr. 4.50 mtr N/A	15 mtr. Provided N/A	MR N/A N/A
02	Number, Width, Type and Arrangement of Exits.			
	a. Number of Staircases <ul style="list-style-type: none"> Upper Floor Basement B. Width of Staircases <ul style="list-style-type: none"> Upper Floor Basement c. Protection of exits <ul style="list-style-type: none"> Fire check door Pressurization d. No. of continuous staircases to terrace <ul style="list-style-type: none"> e. Width of Corridor <ul style="list-style-type: none"> f. Door Size <ul style="list-style-type: none"> 	03 nos. N/A 1.50mtr. N/A N/A N/A 01 nos. 1.50 mtr. 01 mtr.	03 nos. N/A. 1.60 m, 1.55m & 1.50 m N/A. N/A N/A 02 nos. Provided 01 mtr.	MR N/A MR N/A N/A N/A MR MR MR
03	Compartmentation.			
	<ul style="list-style-type: none"> Fire check door Sealing of electrical shafts Fire rating of shaft door Water curtain Fire Dampers 	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A
04	Smoke Management System.			
	<ul style="list-style-type: none"> Basement Upper floor 	N/A N/A	N/A N/A	N/A N/A
05.	Fire Extinguishers.			
	<ul style="list-style-type: none"> Total numbers Types IS marking 	35 nos. ABC /CO ₂ ISI marked	35 nos. ABC /CO ₂ ISI marked	MR MR MR

06	First-aid-Hose Reels.			
	• Total numbers on each floor	03 nos.	03 nos.	MR
	• Length of hose reel hose	30 m	30 m	MR
	• Nozzle diameter	05 mm	05 mm	MR
07	Automatic fire detection and alarming system.			
	• Type of detectors	N/A	N/A	N/A
	• Location of main panel	N/A	N/A	N/A
	• Location of repeater panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooter's location	N/A	N/A	N/A
08	MOEFA	N/A	Provided	N/A
09	Public address System.	N/A	Provided	N/A
10	Automatic Sprinkler System.			
	• Basement	N/A	N/A	N/A
	• upper floor	N/A	N/A	N/A
	• sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants			
	• size of riser/down-comer	100 mm	100 mm	MR
	• Number of hydrants per floor	03 nos.	03 nos.	MR
	• Hose Box	03 nos.	03 nos.	MR
12	Yard Hydrants.			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13	Pumping Arrangements.			
	➤ Ground Level	N/A	N/A	N/A
	• Discharge of main Pump	N/A	N/A	N/A
	• Head of Main Pump	N/A	N/A	N/A
	• Number of main pumps	N/A	N/A	N/A
	• Jockey pump out put	N/A	N/A	N/A
	• Jockey pump head	N/A	N/A	N/A
	• Standby pump out put	N/A	N/A	N/A
	• Standby pump Head	N/A	N/A	N/A
	• Auto Starting /Manual stopping	N/A	N/A	N/A
	• Pump House Access	N/A	N/A	N/A
	➤ Terrace Level			
	• Discharge of pump	450 lpm	450 lpm	MR
	• Head of the Pump	40 mtr	40 mtr	MR
	• Power supply	Required	Provided	MR
	• Auto Starting of pump	Required	Provided	MR
14	Captive Water Storage for Fire Fighting.			
	• Underground tank capacity	N/A	N/A	N/A
	• Draw-off connection	N/A	N/A	N/A
	• Fire service inlet	N/A	N/A	N/A
	• Access to tank	N/A	N/A	N/A
	• Overhead Tank capacity	10,000 ltr	20,000 ltr	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication in lift car	N/A	N/A	N/A
	• Firemen's grounding switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A

17	Standby power supply	N/A	N/A	N/A
18	Refuge Area.			
	• Total area	N/A	N/A	N/A
	• Location	N/A	N/A	N/A
19	Fire Control Room			
	• Detector system panel	N/A	N/A	N/A
	• Flow switch panel	N/A	N/A	N/A
	• PA system panel	N/A	N/A	N/A
	• Battery backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20	Special Fire Protection systems for protection of special Risks, if any:	N/A	N/A	N/A

Note:- The Management has submitted undertaking place at C-44, that Porta cabin constructed at terrace has been closed and will not be used any purpose.

The fire protection systems provided in the building were tested/checked and found functional at the time of inspection.

Keeping in view the deemed compliance of the minimum standards on fire prevention and fire safety measures as required under the rule. The FSC issued vide letter no. F.6/DFS/MS/School/2022/NDZ/164 dt 11/02/2022 renewal under rule 35 of the Delhi Fire Service Rules, 2010 is recommended.

Deepak
01/04/2025
Signature of the Inspecting Officer
Name :- Deepak Kumar
Designation :- A.D.O (Shd)

A.K. Jaiswal
14/4/2025
Signature of the Inspecting Officer
Name :- A.K. Jaiswal
Designation :- D.O (ED)

Dy. C.F.O. (NDZ)
22/04/25

C.F.O.
13/4/2025
Director
11/4/25

D.O. (ED)
ADD/SHD.

F5 letter is put up for your
kind signature pl.

Director
14/4/25

Deepak
01/04/2025