



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE, NEW DELHI-110001



No. F6/DFS/MS/2025/WZ/441

Dated: 20/08/2025

FIRE SAFETY CERTIFICATE

Certified that the **Delhi Metro Rail Corporation Ltd. at Rohini East Metro Station of Line 1, Rohini, Delhi-110085**, comprised of **Ground + Concourse + Platform** has already been issued FSC by this department vide letter No. **F.6/DFS/MS/2022/WZ/408 dated 15.09.2022**. The premises was re-inspected by the officer concerned of this department on **26.07.2025** in the presence of **Mr. Sanjay Jain (Fire Manager)** and found that the said building have deemed complied with the fire prevention and fire safety requirements in accordance with Rule 33 of the Delhi Fire Service Rules, 2010 and that the premises fit for occupancy class '**D**' **Assembly Building** with effect from 20/08/2025 for a period of **three years** in accordance with Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subjected to compliance of the conditions under Rule 38 of the Delhi Fire Service Rules, 2010.

Issued on 20/08/2025 at New Delhi by

19/8/2025

(Virendra Singh)
Chief Fire Officer
Delhi Fire Service

Copy to :-

1. Sh. Rajesh Aggarwal (GM/E&M), Metro Bhawan, Fire Brigade Lane, Barakhamba Road, New Delhi-110001.

Conditions for the validity of fire safety certificate:

1. All the fire safety arrangement provided there-in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director of Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".
7. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on
8. All the means of escape shall be kept free of any obstruction all the time to evacuate the occupant, in a safe manner, in the event of emergency.

http://www.delhi.gov.in/wps/wcm/connect/doit_fire/FIRE/Home/Fire+Safety+Acts+and+Rules/
http://www.delhi.gov.in/wps/wcm/connect/doit_fire/FIRE/Home/Forms

INSPECTION REPORT

1. Name & address of the building : Delhi Metro Rail Corporation Ltd. at Rohini East Metro Station of Line 1, Delhi-110085.
2. Type of Occupancy : Assembly
3. Type of Case : Renewal (**Ground Level + Concourse Level + Platform Level**)
4. Details of Previous NOC : F.6/DFS/MS/2022/WZ/408 dated 15.09.2022.
5. Fire Safety directives letter No : N/A
6. Date of inspection : 26.07.2025.
7. Name of Inspecting Officer : A.K.Sharma ADO(Rohini)
8. Name and designation of officers
From the building side : Mr. Sanjay Jain (Fire Manager)
9. Year of Construction : 2004
10. Applicant's letter No. : OD No.3462 dated 07.07.2025.

| S. No. | Minimum Standards on fire prevention and fire safety U/R 33 | NBC Requirement | Provided at site | Remarks MR/NMR |
|--------|---|--|--|--------------------------------|
| 1. | Access to building | | | |
| | <ul style="list-style-type: none"> Road width Gate width Width of internal road | 21m 5m -NA- | 21m NA -NA- | MR NA -NA- |
| 2. | Number, Width, Type & Arrangement of Exits | | | |
| | a. Number of staircases | | | |
| | <ul style="list-style-type: none"> Upper Floors Basements | 04 nos. Concourse to platform 03 nos. Ground to Concourse -NA- | Provided -NA- | MR -NA- |
| | b. Width of staircases | | | |
| | <ul style="list-style-type: none"> Upper Floor Basements | 1.5m -NA- | Provided -NA- | MR -NA- |
| | c. Protection of exits | | | |
| | Fire check door | Required | Provided | MR |
| | <ul style="list-style-type: none"> Pressurization | -NA- | -NA- | -NA- |
| | d. No. of continuous staircases to terrace | 02nos. | Provided | MR |
| | e. Width of Corridor | -NA- | -NA- | -NA- |
| | f. Door Size | 1.0m | 1.0m | MR |
| 3. | Compartmentation | | | |
| | <ul style="list-style-type: none"> Fire check door Sealing of electrical shafts Fire Rating of shaft door Water Curtain Fire Dampers | Required Required Required -NA- -NA- | Provided Provided Provided -NA- -NA- | MR MR MR -NA- -NA- |
| 4. | Smoke Management System | | | |
| | <ul style="list-style-type: none"> Basements Upper floors | -NA- 12 a/c per hour | -NA- Natural ventilated | -NA- MR |
| 5. | Fire Extinguishers | | | |
| | <ul style="list-style-type: none"> Total numbers Types ISI marking | 28nos. ABC/CO2 ISI marked | Provided ABC/CO2 Yes | MR MR MR |
| 6. | First-Aid Hose Reels | | | |
| | <ul style="list-style-type: none"> Total numbers on each floor Length of hose reel hose Nozzle diameter | 02 on each platform 04 on Concourse/Plat form 45mm 5m | Provided Provided Provided | MR MR MR |
| 7. | Automatic fire detection and alarming system | | | |
| | <ul style="list-style-type: none"> Type of detectors Location of Main Panel Location of Repeater Panel | Smoke Required -NA- | Provided Provided -NA- | MR MR -NA- |

| | | | | |
|-----|---|-----------|-------------------|------|
| | <ul style="list-style-type: none"> Alternate source of power Hooters' Location | Required | Provided | MR |
| | | Required | Provided | MR |
| 8. | MOEFA | Required | Provided | MR |
| 9. | Public Address System | Required | Provided | MR |
| 10. | Automatic Sprinkler System | | | |
| | <ul style="list-style-type: none"> Basement Ground & Upper Floors Sprinkler above false ceiling | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| 11. | Internal Hydrants | | | |
| | <ul style="list-style-type: none"> Size of riser/down-comer Number of hydrants per floor Hose Box | 80mm | Provided | MR |
| | | Required | Same as col. no.6 | MR |
| | | Required | Same as col. no.6 | MR |
| 12. | Yard Hydrants | | | |
| | <ul style="list-style-type: none"> Total number of hydrants Hose Box | 02nos. | Provided | MR |
| | | Required | Provided | MR |
| 13. | Pumping Arrangements | | | |
| | <ul style="list-style-type: none"> Ground Level ➤ Discharge of main Pump ➤ Head of Main pump ➤ Number of main pumps ➤ Jockey Pump out put ➤ Jockey pump head ➤ Standby Pump out put ➤ Standby Pump Head ➤ Auto Starting/Manual Stopping ➤ Pump House Access | 1800lpm | 1800lpm | MR |
| | | 60m | 60m | MR |
| | | 01 | 01 | MR |
| | | 180lpm | 180lpm | MR |
| | | 60m | 60m | MR |
| | | 180lpm | 180lpm | MR |
| | | 60m | 60m | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | <ul style="list-style-type: none"> Terrace level ➤ Discharge of pump ➤ Head of the pump ➤ Power Supply ➤ Auto Starting of pump | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| 14. | Captive Water Storage for fire fighting | | | |
| | <ul style="list-style-type: none"> Underground tank capacity ➤ Draw-off connection ➤ Fire service inlet ➤ Access to tank Overhead Tank capacity | 100 KL. | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | 10,000ltr | 10,000ltr | MR |
| | | Required | Provided | MR |
| 15. | Exit Signage. | | | |
| 16. | Provision of Lifts. | | | |
| | <ul style="list-style-type: none"> Pressurization of Lift Shaft Pressurization of Lift lobby Communication In lift Car Fireman's Grounding Switch Lift Signage | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| 17. | Standby power supply | | | |
| 18. | Refuge Area. | | | |
| | <ul style="list-style-type: none"> ➤ Total Area ➤ Location | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| 19. | Fire Control Room | | | |
| | <ul style="list-style-type: none"> Detector System Panel Flow Switch Panel PA System Panel Battery backup Building Floor Plans | Required | Provided | MR |
| | | -NA- | -NA- | -NA- |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | -NA- | -NA- | -NA- |

| | | | | |
|-----|---|----------|----------|----|
| 20. | Special Fire Protection System for Protection of special Risks, if any: | Required | Provided | MR |
|-----|---|----------|----------|----|

Accordingly, the fire protection systems provided in the building were tested/ checked randomly and found in working condition at the time of inspection.

In view of the deemed compliance of the minimum standards of the fire prevention and fire safety measures as required under the rules the FSC issued vide letter no. **F.6/DFS/MS/2022/WZ/408** dated **15.09.2022** is recommended for renewal of FSC under rule 37 of the Delhi Fire Service rules 2010.

Ajay
11/8/25

Signature of the Inspecting Officer
Name Ajay Kumar Sharma
Designation ADO(Rohini)

DO (NW)

CFO/267...NW
ated...05/08/25

Ajay
04/08/2025

Ajay
04/08/2025

Ajay
05/08/2025

CFO/
Ajay
12/8/2025

Principal Director

CFO to Issue.

Ajay
12/08/25

CFO/
Ajay

ADO (Rohini)

FT letter to put up for kind perusal
and signature per.

Ajay
18/8/25

CFO/
Ajay
19/8/2025

MS