



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE  
NEW DELHI- 110 001

No. F.6/DFS/MS/School/2025/NDZ/ 585

Dated: 02/05/2025

**FIRE SAFETY CERTIFICATE**

Certified that Gyan Sarover Public School is running ground to second floor the building comprised of ground plus three upper floors (third floor sealed) located at B 2/413 Subhash Kansal Marg, Harsh Vihar, Delhi-110093, comprised of ground plus three upper floors only, owned/occupied Gyan Sarover Public School was issued FSC vide letter No. F.6/DFS/MS/School/2021/NDZ/871 dated 25/10/2021. The premises was re-inspected by the officer concerned of this department on dated 07/04/2025 in the presence of Mr. Arvind Gupta and found that all the fire prevention and fire safety arrangements provided in the premises found in good working condition. The premises have complied with the fire prevention and fire safety requirements in accordance rules 33 of the Delhi Fire Service Rules, 2010 and that the building/premises is fit forground plus two floors only occupancy class 'Educational (Group-B)' with effect from 02/05/2025 for a period of three years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010 & also conditions printed below.

Issued on 02/05/2025 at New Delhi by

(ATUL GARG)  
DIRECTOR

DELHI FIRE SERVICE

To:-

The Manager,  
Gyan Sarover Public School,  
B 2/413 Subhash Kansal Marg, Harsh Vihar, Delhi-110093

Copy to:-

The Dy. Director of Education  
B-Block Yamuna Vihar, Delhi-110053

**Conditions for the validity of Fire Safety Certificate**

1. FSC is valid for ground plus two upper floors only. Third floor which is sealed may and not be used for any purpose failing which FSC should be treated null and void.
2. All the means of escape shall be kept free of all type of obstruction all the time.
3. All the employees shall be acquainted with the use and maintenance of all fire equipments and method of smooth and speedy safe evacuation of occupants in case of emergency.
4. All the fire fighting equipment shall be maintained in perfect working condition all the time and any lapse rendering non-functional of fire safety measures, management shall be responsible.
5. Any deviation, with regards to construction, ventilation, occupancy, electric installation etc. may be got verified from the concerned authorities.
6. This Fire Safety Certificate may not be treated in any case for regularizations of unauthorized construction /unauthorized use of land if any.
7. The owner / occupier shall apply for renewal of this Fire Safety Certificate of the Director in Form 'J' [sub rule (1) of rule (37)] along with a copy of this Certificate, Six Months prior to its expiry.
8. The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rule 2010. The form is available on [www.dfs.delhigovt.nic.in](http://www.dfs.delhigovt.nic.in)

## INSPECTION REPORT

1. Name & address of the building : Gyan Sarover Public School, at B 2/413  
Subhash Kansal Marg, Harsh Vihar, Delhi-110093
2. Building is comprised of : Ground Plus three upper floors, but School is running on  
ground +2 upper floors only (Third floor sealed)
3. Type of Occupancy : Educational
4. Type of Case : Renewal
5. Details of Previous NOC letter : F.6/DFS/MS/School/2021/NDZ/871 dated 25/10/2021
6. Fire Safety direction letter No : NBC Part-IV
7. Date of Inspection : 07/04/2025
8. Name of the Inspecting officers : ADO (Shd.) Deepak Kumar
9. Name and designation of Officer  
from the building side : Mr. Arvind Gupta
10. Year of Construction : 2004
11. Applicant's letter No : Outdoor Diary No. 12419 dated 13/02/2025

Sr. No	Minimum Standards on fire prevention and fire safety U/R33	NBC Part-IV Requirement	Provided at Site	Remarks MR/NMR
01	Access to building.			
	<ul style="list-style-type: none"> <li>Road width</li> <li>Gate width</li> <li>Width of internal road</li> </ul>	06 mtr. N/A N/A	06 mtr. N/A N/A	MR N/A N/A
02	Number, Width, Type and Arrangement of Exits.			
	a. Number of Staircases			
	<ul style="list-style-type: none"> <li>Upper Floor</li> <li>Basement</li> </ul>	01 nos. N/A	02 nos. N/A.	MR N/A
	B. Width of Staircases			
	<ul style="list-style-type: none"> <li>Upper Floor</li> <li>Basement</li> </ul>	1.50 mtr. N/A	1.60 mtr. & 0.90 mtr N/A.	MR N/A
	c. Protection of exits			
	<ul style="list-style-type: none"> <li>Fire check door</li> <li>Pressurization</li> </ul>	N/A N/A	N/A N/A	N/A N/A
	d. No. of continuous staircases to terrace	01 nos.	01 nos.	MR
	e. Width of Corridor	1.50 mtr.	1.50 mtr.	MR
	f. Door Size	01 mtr.	1 .05 mtr.	MR
03	Compartmentation.			
	<ul style="list-style-type: none"> <li>Fire check door</li> <li>Sealing of electrical shafts</li> <li>Fire rating of shaft door</li> <li>Water curtain</li> <li>Fire Dampers</li> </ul>	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A
04	Smoke Management System.			
	<ul style="list-style-type: none"> <li>Basement</li> <li>Upper floor</li> </ul>	N/A N/A	N/A N/A	N/A N/A
05.	Fire Extinguishers.			
	<ul style="list-style-type: none"> <li>Total numbers</li> <li>Types</li> <li>IS marking</li> </ul>	06 nos. ABC /CO <sub>2</sub> ISI marked	07 nos. ABC /CO <sub>2</sub> ISI marked	MR MR MR



N/18

06	First-aid-Hose Reels.			
	• Total numbers on each floor	01 nos.	01 nos.	MR
	• Length of hose reel hose	30 mrt	30 mrt	MR
	• Nozzle diameter	05 mm	05 mm	MR
07	Automatic fire detection and alarming system.			
	• Type of detectors	N/A	N/A	N/A
	• Location of main panel	N/A	N/A	N/A
	• Location of repeater panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooter's location	N/A	N/A	N/A
08	MOEFA	N/A	N/A	N/A
09	Public address System.	N/A	N/A	N/A
10	Automatic Sprinkler System.			
	• Basement	N/A	N/A	N/A
	• upper floor	N/A	N/A	N/A
	• sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants			
	• size of riser/down-comer	N/A	N/A	N/A
	• Number of hydrants per floor	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
12	Yard Hydrants.			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13	Pumping Arrangements.			
	➤ Ground Level	N/A	N/A	N/A
	• Discharge of main Pump	N/A	N/A	N/A
	• Head of Main Pump	N/A	N/A	N/A
	• Number of main pumps	N/A	N/A	N/A
	• Jockey pump out put	N/A	N/A	N/A
	• Jockey pump head	N/A	N/A	N/A
	• Standby pump out put	N/A	N/A	N/A
	• Standby pump Head	N/A	N/A	N/A
	• Auto Starting /Manual stopping	N/A	N/A	N/A
	• Pump House Access	N/A	N/A	N/A
	➤ Terrace Level			
	• Discharge of pump	450 lpm	450 lpm	MR
	• Head of the Pump	40 mtr	40 mtr	MR
	• Power supply	Required	Provided	MR
	• Auto Starting of pump	Required	Provided	MR
14	Captive Water Storage for Fire Fighting.			
	• Underground tank capacity	N/A	N/A	N/A
	• Draw-off connection	N/A	N/A	N/A
	• Fire service inlet	N/A	N/A	N/A
	• Access to tank	N/A	N/A	N/A
	• Overhead Tank capacity	10,000 ltrs	10,000 ltrs	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication in lift car	N/A	N/A	N/A
	• Firemen's grounding switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A

2. ✕

17	Standby power supply	N/A	N/A	N/A
18	Refuge Area.			
	• Total area	N/A	N/A	N/A
	• Location	N/A	N/A	N/A
19	Fire Control Room			
	• Detector system panel	N/A	N/A	N/A
	• Flow switch panel	N/A	N/A	N/A
	• PA system panel	N/A	N/A	N/A
	• Battery backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20	Special Fire Protection systems for protection of special Risks, if any:	N/A	N/A	N/A

**Note:- The school management has submitted undertaking, third floor is sealed and not used for any purpose (attached at C/27).**

The fire protection systems provided in the building were tested/checked and found functional at the time of inspection.

Keeping in view the deemed compliance of the minimum standards on fire prevention and fire safety measures as required as per rule. The FSC issued vide letter no. F.6/DFS/MS/School/2021/NDZ/871 dated 25/10/2021 renewal under rule 35 of the Delhi Fire Service Rules, 2010 is recommended.

*Deepak* 05/04/2025  
Signature of the Inspecting Officer  
Name :- Deepak Kumar  
Designation :- A.D.O (Shd)

DO(ED) *[Signature]* 09/04/2025

Dy. C.F.O. (NDZ)

*Ring* 11/04/25

C.F.O.

*Ring* 21/4/2025

Random 29/4/25

Director *[Signature]*

29/4/25

AOV/SHD

Sir, as letter is put up for your kind signature pl.

Director *[Signature]*

*Deepak* 30/04/2025