



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE, NEW DELHI-110001



No. F6/DFS/MS/2025/WZ/College/ 32

Dated: 11/09/2025

FIRE SAFETY CERTIFICATE

Certified that the Rukmani Devi Institute of Advance Studies, 2-A & 2-B, B-Block, Madhuban, Chowk, Rohini, Delhi-110085, comprised of Basement + Ground + 03 upper floors has already been issued FSC by this department vide letter No. F.6/DFS/MS/2022/WZ/College/16 dated 18.10.2022. The premises was re-inspected by the officer concerned of this department on 25.08.2025 in the presence of Dr. Raman Garg (Director) and found that the said building have deemed complied with the fire prevention and fire safety requirements in accordance with Rule 33 of the Delhi Fire Service Rules, 2010 and that the premises fit for occupancy class "Group B Educational" with effect from 11/09/2025 for a period of three years in accordance with Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subjected to compliance of the conditions under Rule 38 of the Delhi Fire Service Rules, 2010.

Issued on 11/09/2025 at New Delhi by

11/09/2025
(Virendra Singh)
Chief Fire Officer
Delhi Fire Service

Copy to :-

1. The Director, Rukmani Devi Institute of Advance Studies, 2-A & 2-B, B-Block, Madhuban, Chowk, Rohini, Delhi-110085.

Conditions for the validity of fire safety certificate:

1. All the fire safety arrangement provided there-in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director of Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".
7. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on
8. All the means of escape shall be kept free of any obstruction all the time to evacuate the occupant, in a safe manner, in the event of emergency.

http://www.delhi.gov.in/wps/wcm/connect/doit_fire/FIRE/Home/Fire+Safety+Acts+and+Rules/
http://www.delhi.gov.in/wps/wcm/connect/doit_fire/FIRE/Home/Forms

INSPECTION REPORT

1. Name & address of the building : Rukmini Devi Institute of Advance Studies, 2-A & 2-B, B-Block, Madhuban, Chowk, Rohini, Delhi-110085.
2. Type of Occupancy : Educational
3. Type of Case : Renewal (Basement + Ground + 03 upper floors) B-Block only
4. Details of Previous NOC : F.6/DFS/MS/2022/WZ/College/16 dated 18.10.2022.
5. Fire Safety directives letter No : F.6/DFS/MS/BP/2003/2314 dated 29.06.2003
6. Date of inspection : 25.08.2025
7. Name of Inspecting Officer : A.K.Sharma ADO(Rohini)
8. Name and designation of officers
From the building side : Dr. Raman Garg (Director)
9. Year of Construction : 2004
10. Applicant's letter No. : OD No.3836 dated 17.07.2025.


S. No.	Minimum Standards on fire prevention and fire safety U/R 33	Rule 35(6)	Provided at site	Remarks MR/NMR
1.	Access to building			MR
	<ul style="list-style-type: none"> Road width Gate width Width of internal road 	12m 4.5m -NA-	18m 5m -NA-	MR MR -NA-
2.	Number, Width, Type & Arrangement of Exits			
	a. Number of staircases	02nos.	03nos.	MR
	<ul style="list-style-type: none"> Upper Floors Basements 	01 s/c & 01 ramp	02 s/c & 01 ramp	MR
	b. Width of staircases	1.5m	I-1.10m to 1.20m II-1.2m to 1.22m III-1.60m to 1.65m	MR (Old case)
	<ul style="list-style-type: none"> Upper Floor Basements 	1.5m & 01 ramp	1.2m x 2 & 01 ramp 2.0m	MR
	c. Protection of exits	Required	Provided	MR
	Fire check door	-NA-	-NA-	-NA-
	<ul style="list-style-type: none"> Pressurization 	01nos.	Provided	MR
	d. No. of continuous staircases to terrace	-NA-	-NA-	-NA-
	e. Width of Corridor	1.0m	1.13m	MR
	f. Door Size			
3.	Compartmentation	Required	Provided	MR
	<ul style="list-style-type: none"> Fire check door Sealing of electrical shafts Fire Rating of shaft door Water Curtain Fire Dampers 	Required	Provided	MR
		-NA-	-NA-	-NA-
		-NA-	-NA-	-NA-
		-NA-	-NA-	-NA-
4.	Smoke Management System	30 a/c per hour	Exhaust fan	MR
	<ul style="list-style-type: none"> Basements Upper floors 	12 a/c per hour	Natural ventilated	MR
5.	Fire Extinguishers	16nos.	Provided	MR
	<ul style="list-style-type: none"> Total numbers Types ISI marking 	ABC/CO2	ABC/CO2	MR
		ISI marked	Yes	MR
6.	First-Aid Hose Reels	01nos.	Provided	MR
	<ul style="list-style-type: none"> Total numbers on each floor Length of hose reel hose Nozzle diameter 	30mm	Provided	MR
		5m	Provided	MR
7.	Automatic fire detection and alarming system	Required	Provided	MR
	<ul style="list-style-type: none"> Type of detectors Location of Main Panel Location of Repeater Panel 	GF	Provided	MR
		-NA-	-NA-	-NA-

	• Alternate source of power	Required	Provided	MR
	• Hooters' Location	At strategic point	Provided	MR
8.	MOEFA	Required	Provided	MR
9.	Public Address System	Required	Provided	MR
10.	Automatic Sprinkler System			
	• Basement	Required	Provided	MR
	• Ground & Upper Floors	-NA-	-NA-	-NA-
	• Sprinkler above false ceiling	-NA-	-NA-	-NA-
11.	Internal Hydrants			
	• Size of riser/down-comer	4"	Provided	MR
	• Number of hydrants per floor	01nos.	Provided	MR
	• Hose Box	01nos.	Provided	MR
12.	Yard Hydrants			
	• Total number of hydrants	-NA-	-NA-	-NA-
	• Hose Box	-NA-	-NA-	-NA-
13.	Pumping Arrangements			
	• Ground Level	-NA-	-NA-	-NA-
	➤ Discharge of main Pump	-NA-	-NA-	-NA-
	➤ Head of Main pump	-NA-	-NA-	-NA-
	➤ Number of main pumps	-NA-	-NA-	-NA-
	➤ Jockey Pump out put	180lpm	Provided	MR
	➤ Jockey pump head	40m	Provided	MR
	➤ Standby Pump out put	-NA-	-NA-	-NA-
	➤ Standby Pump Head	-NA-	-NA-	-NA-
	➤ Auto Starting/Manual Stopping	-NA-	-NA-	-NA-
	➤ Pump House Access	-NA-	-NA-	-NA-
	• Terrace level			
	➤ Discharge of pump	1620lpm	1620lpm	MR
	➤ Head of the pump	40m	40m	MR
	➤ Power Supply	-NA-	-NA-	-NA-
	➤ Auto Starting of pump	-NA-	-NA-	-NA-
14.	Captive Water Storage for fire fighting			
	• Underground tank capacity	50,000ltr	50,000ltr	MR
	➤ Draw-off connection	Required	Provided	MR
	➤ Fire service inlet	Required	Provided	MR
	➤ Access to tank	Required	Provided	MR
	• Overhead Tank capacity	20,000ltr	20,000ltr	MR
15.	Exit Signage.	Required	Provided	MR
16.	Provision of Lifts.			
	• Pressurization of Lift Shaft	-NA-	-NA-	-NA-
	• Pressurization of Lift lobby	-NA-	-NA-	-NA-
	• Communication In lift Car	Required	Provided	MR
	• Fireman's Grounding Switch	Required	Provided	MR
	• Lift Signage	Required	Provided	MR
17.	Standby power supply	Required	125KVA	MR
18.	Refuge Area.			
	➤ Total Area	-NA-	-NA-	-NA-
	➤ Location	-NA-	-NA-	-NA-
19.	Fire Control Room			
	• Detector System Panel	-NA-	-NA-	-NA-
	• Flow Switch Panel	-NA-	-NA-	-NA-
	• PA System Panel	-NA-	-NA-	-NA-
	• Battery backup	-NA-	-NA-	-NA-
	• Building Floor Plans	-NA-	-NA-	-NA-

1R	Special Fire Protection System for Protection of special Risks, if any:	-NA-	-NA-	-NA-
----	---	------	------	------

Accordingly, the fire protection systems provided in the building were tested/ checked randomly and found in working condition at the time of inspection.


In view of the deemed compliance of the minimum standards of the fire prevention and fire safety measures as required under the rules the FSC issued vide letter no. F.6/DFS/MS/2022/WZ/College/16 dated 18.10.2022 is recommended for renewal of FSC under rule 37 of the Delhi Fire Service rules 2010.



 Signature of the Inspecting Officer
 Name Ajay Kumar Sharma
 Designation ADO(Rohini)

DO (NW)



 25/08/2025
 Dy. CPO (WZ)



 29/8




 2/9/2025
 Principal Director

CFO to J. Sec.

 23/09/25


 6/9/


 Dy CPO WZ
 put-up F.T.


 8/9
 ADO (Rohini)
 FT letter is put up for kind
 perused and signature please.


 CFO
 10/9/25
 MS

 10/9/25

DCFO/...30/6/2025
 Dated...29/8/2025