



**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE
NEW DELHI- 110 001**

No.F.6/DFS/MS/Hospital/2026/694

Dated: 27.04.2026

To,

Dr. Abdul Khaliq,
Samra Hospital,
C-3/52A-53A, Yamuna Vihar
Delhi-110053

Subject: -Regarding issuance of Fire Safety Certificate in r/o Samra Hospital located at C-3/52A-53A, Yamuna Vihar, Delhi-110053.

Sir,

This is in reference to your letter no. F.24/North East District/DGHS/NHC370-71 dated 03/02/2026 received on dated 03/02/2026 in this department on the subject cited above. In this connection, it is to informed you that this department has already sent its reply letter vide letter no. F.6/DFS/MS/Hospital/2025/NDZ/2165 dated 17/12/2025 (Copy enclosed).

In view of the above Fire Safety Certificate cannot be considered at this stage.

Yours faithfully

Encl. As above


(Dr. S. K. TOMAR)
CHIEF FIRE OFFICER
DELHI FIRE OFFICER

Copy to:-

1. The Directorate of Health Service, M.O. I/C Nursing Home Cell, Govt. of NCT of Delhi, F-17, Karkardooma, Delhi-110032



No. F6/DFS/MS/Hospital/NDZ/2025/ 313

Dated: 30/06/2025

Dr. Abdul Khalique
Samra Hospital,
C-3/52A-53A, Yamuna Vihar,
Delhi - 110053.

Subject: - Regarding grant of Fire Safety Certificate in r/o Samra Hospital located at C-3/52A-53A, Yamuna Vihar, Delhi - 110053.

Sir,

This has a reference to Outdoor Diary No. 1953 dated 21/05/2025, on the subject cited above. In this connection, it is to inform you that premises was inspected by the officers concerned of this department on 23/06/2025 in the presence of Dr. Abdul Khalique and observed that building comprised of Basement, ground plus two upper floors only.

Following shortcomings were observed during time of inspection:

1. Two staircase of width 1.15 meters & 0.92 meters (upto 1st floor only) are provided instead of required width of 2.0 & 1.50 meter respectively on ground floor.
2. Two staircase of width 1.13 meters & 1.16 meters are provided instead of required width of 2.0 & 1.50 meter respectively in basement.
3. Fire check door not provided.
4. The corridor of width 1.49 meters against the requirement of 2.40 meters.
5. The width of door size is 0.95 meter against the requirement of 1.50 meter.
6. Smoke Management System not provided in basement and upper floors.
7. First-Aid-Hose Reel not provided.
8. Automatic Sprinkler System not provided in basement.
9. Internal Hydrants not provided.
10. Pumping arrangements one electric pump of 1620 LPM, one jockey pump of 180 LPM and one diesel pump of 1620 LPM fire pump not provided.
11. Terrace fire pump of 900 LPM capacity is not provided.
12. Underground water storage tank capacity 75,000 liters not provided.
13. Overhead water storage tank capacity 10,000 liters not provided.
14. Exit & floors Signage's not provided at strategic location in the building.
15. Pressurization of lift shaft in basement not provided.
16. Lift signage's not provided.
17. Standby Power Supply not provided.

In view of above shortcomings, the application for issuance for Fire Safety Certificate is rejected. The occupancy of the building/premises in absence of requisite fire safety arrangements shall be at the risk and liability of the management. The Authority/Statutory Authority may take suitable necessary action as deemed fit.

Yours faithfully,

(ATUL GARG)
DIRECTOR

O/C DELHI FIRE SERVICE

Copy to: -

1. The Medical Superintendent, Nursing Homes, Directorate General of Health Services, Govt. of NCT of Delhi, 3rd floor, Delhi Govt. Dispensary Building, S-1, School Block, Shakarpur, Delhi - 110032.